

CNGS Horns




• CNGS Horns

- Introduction
- Design
- « Remote »
- Timing tests

• Horn exchange

- Striplines
- Procedure
- Exchange Exercise

Introduction



Introduction




- Weight ~1.2t (Reflector: 1.8t)
- 7 meters long, inner & outer conductor
- Upper frame (exchange) & lower frame (align)
- **Electric (manual)** & water connections (automatic)

at downstream end


Inner conductor



© LAL, Paris



- Thickness 1.8 mm
- Aluminum grade 6082
- 9 machined sections
- Electron beam welds



Support Points (3)

3x3 grooves in inner conductor



S.Steel cables



Insulator



Outer conductor

Heat load horn:

15 kW (Joule)

+ 6 kW (beam)

Cooling through top sprayers, 1.2 bar

Magnetic field:
Max. 1.5 Tesla

Designed for remote handling



Pre-guiding elements, cameras, remotely steered crane, cameras, plug-in water connection...




Pre-guiding upper frame vs. lower frame



28/08/2006

Crane with coordinates
Ans PARDONS

Plug-in Water Connection



28/08/2006


Ans PARDONS

Grafoil seals




Grafoil seal

- 98% pure graphite
→ Resists high radiation
- Needs only ~5MPa contact pressure




Other applications:

- Two way-valve with spherical graphite seal (switching between water feed circuits)
- Seal between insulating glass disk and plates of electrical connection
("glass disk assembly")



Decoupled Frames




Seal contact force (from spring) = 2000N

To absorb force

- Need for rigid frames
- Fix collector tube to rigid upper frame




**In case
of horn
exchange**





Goes away
with horn

Stays in
place



Installation




**Fast Coupling Connection
(horn exchange)**

28/08/2006


Ans PARDONS

Timing: Vibration tests

(courtesy of R. Wilfinger CERN/TU Vienna)



In target chamber
(new horn)
In test stand
(old horn & new horn)



→ Natural frequency horn: 149Hz (reflector: 73Hz)


→ Data collected for future study of effect of

- Cooling water temperature
- Glass disk assembly

Vibration tests



(courtesy of R. Wilfinger CERN/TU Vienna)




→ Optimum of 50ms gap for horn
(less fragile reflector: optimum @48ms, +20% @50ms)


Timing: pulse start



During commissioning:




Electrical Pulse Timing



Vary from -2ms to 2ms
w.r.t. nominal,
Measure muons

Conclusion of successful commissioning (400000 pulses):
CNGS Horn design validated
(glass disk, water circuit, inner conductor,...)

Horn exchange



Fatigue → Life time of horn
(95% confidence):
20 million pulses = 5 years

Highly radioactive zone:
→ Maximize remote & automatic
→ Minimize dose

- Define detailed procedure
(interaction with RP^(*) experts)
- Do complete exercise
(realistic conditions)
- Documentation (photo, film)
is extremely important!

Define procedure




- Design phase: Optimization with respect to dose
- Experience → First draft of procedure
- Input to HAZOP study (*)
 - main remaining risks identified
- New version written with input from study & experts (radioprotection, handling, transport, ...)
- Tools designed, produced & tested
- Steps were tested & timed → optimisation
- 100% remote handling (shielding):
 - Tested → coordinates noted down in worksheets

→ Updated procedure = script for exercise


Striplines



- 16m long aluminum plates
- 8 plates of 12mm each
- 8mm isolating rings between plates
- Cu/Ag for flexible link sections




Horn exchange procedure



- Disconnect Fast Coupling
- Take out Stripline Link
- Move stripline (open)
- → horn disconnected
- Open shielding (roof & side wall)
- Exchange horn remotely
- Close shielding
- Move stripline (close)
- → horn reconnected
- Put Stripline Link back
- Connect Fast Coupling



Fast Coupling Connection



Stripline Link Section

Disconnect Fast Coupling



Fast Coupling

Stripline Link
(rigid plates)

(with shielding in place)



before

after



Move stripline down
(open)



→ Fast Coupling is disconnected

Ans PARDONS

Open shielding



before




after

100% Remote



« mushrooms »
as guide



Overhead crane
with coordinates



Cameras

28/08/2006

Ans PARDONS

18

Remove old horn & Install new



100% Remote (radioactive)



from: target chamber
to : radioactive storage



28/08/2006

Ans PARDONS

50% Remote (clean)



Close shielding



before



100% Remote



Storage blocks



after



Crane coordinates recorded during exercise

28/08/2006



Connect Fast Coupling



Move stripline up



Fix 5 bolts,
install
8 plates

→ Fast Coupling is closed

Horn exchange exercise



Final test = complete exchange

- Realistic conditions:
 - Suits, gloves, masks
 - Lighting, location
- Locations photographed (storage, intervention)
- Every step filmed (except if 100% remote)
- Every step timed and observed by RP experts
- With last inputs → final documents



Detailed procedure **Worksheets (crane/human)** **Tools description** **Film Photos** **Mock-up for training**

Conclusion of successful horn exchange:
CNGS Horn exchange procedure validated
Through documentation, tools, mock-up → knowledge remains



Info (26/8) from J. Hysten on Numi horns ceramic failure (leak)



“For both ceramics that we have replaced, the ceramic that leaks is mostly hidden behind a shroud, and we have not yet done an autopsy to look directly at what failed.

For what it is worth, we are guessing that the braze joint is corroding or otherwise failing, and are thinking of switching to shrink-fit connection to the ceramics.

The ceramics that we can see directly (the one between horn inner and outer conductors, the ones mounting the stripline, the ones holding the shrouds) look fine other than color changes.

The ceramics were both on water cooling circuits.

There is a flex-hose between the ceramic and the water header mounted directly on the horn, so the ceramic is somewhat insulated from the horn vibration, although vibration can still travel through the horn mounting to the hanger bracket and back to the ceramic.”

extra slide

Short movies




Preview:




Move the Stripline Link
(upstream) (2'40'')

Starring Victor De Jésus


extra slide Horn Design



Outlet
cooling water



Isolated Link
Cradles
Water Collector
Upper / Lower frame
Alignment & Feet
Coaxial Plug-in
Water Connection (*)
Water in / out
(*) remark review 2004



extra slide

Horn exchange: HAZOP




Hazard & Operability study for horn exchange

- 1) write specification
(incl. Horn exchange procedure)
 - 2) make call for tender (at least 5 companies)
 - 3) choose company, agree on dates
- > agree on sequences in horn exchange procedure
 - > agree on keywords

 - > HAZOP meeting (2.5 days) 15-17 June 2005
 - > approve minutes
 - > follow-up on "actions"
 - > review actions (phone conference)
 - > presentation of HAZOP report 2 Sept. 2005

extra slide

Horn Exchange: Stripline



Fast Coupling:
5 nuts (manual,
through shielding)

Stripline Link:
8x10x2 screws
(pneumatic in
trench)

Ans PARDONS

